



CALIFA DAQ Readout and Electronics status update



Tobias Jenegger

R³B Week May 2023

Current Status

Filling CEPA

Final Electronics Configuration

Funded by the Deutsche Forschungsgemeinschaft (DFG, German Research Foundation) under Germany's Excellence Strategy – EXC-2094 – 390783311, BMBF 05P19W0FN1, 05P21W0FN1 and the FAIR Phase-0 program









TUM Members: Roman Gernhäuser,Lukas Ponnath,Philipp Klenze,Tobias Jenegger



Where is CALIFA?









Meanwhile in R³B Preparation ROOM





- Noise debugging
- Cable/connectors checking
- Etc.
- More in Stefan Eder's talk






Filling CEPA



- Most forward section: $7^{\circ} \le \theta \le 19^{\circ}$
- 96 CsI crystals


Mesytec MPRB-48 Dual Range Preamps

They get mounted on iPhos tiles



Connected to iPhos APDs (32 channels)


Connected to CEPA APDs (16 channels)





CALIFA Configuration (S522, 2022)





iPhos:

- completely filled
- readout with Dual Range Preamps

Barrel:

- Half filled (Ring 3&4)
- Readout with Single Range (300/30 MeV) Preamps

Pulser:


- 2 SR 100/10 MeV Preamps
- For deadtime/sync checking



CALIFA DAQ Status (S522, 2022)







Electronic Rack

- 8 Crates (each with 18 x FEBEX + Addon)
- 2 PCs (with Knipex+TRIXOR)
- 2 TDK Lambda
- 4 Exploder
- 1 "Overlord" Exploder
- 2 Slow Control PCs

Cables

- 32 SCSI data cables (iPhos)
- 64+2 SR data cables (Barrel)
- 48 LV power cables






What do we have still in Stock?



Missing compared to order status








Stock

Missing compared to order status







Possible Electronics Configurations


Tobias Jenegger 10



Default Configuration



CEPA		iPhos	Ring 4	Ring 3	Ring 2	Ring 1
		DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
	DR 48 30/300 DR 48 30/300 SR 30/300 SR 30/300 DR 48 30/300 DR 48 30/300 DR 48 30/300 SR 30/300 SR 30/300 30/300			SR 30/300	SR 30/300	SR 10/100
				SR 30/300	SR 30/300	SR 10/100
				SR 30/300	SR 30/300	SR 10/100
			SR 30/300	SR 30/300	SR 10/100	
		DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100







4π Configuration



CEPA		iPhos	Ring 4	Ring 3	Ring 2	Ring 1	
DR 30/300		DR 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 48 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 48 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 48 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 48 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100
		DR 30/300	DR 30/300	SR 30/300	SR 30/300	SR 30/300	SR 10/100






Second Rack on each side needed!



Mixed Configuration



CI	EPA	iPhos	Ring 4	Ring 3	Ring 2	Ring 1
		DR 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
		DR 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
		DR 48 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
		DR 48 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
		DR 48 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
		DR 48 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
	1	DR 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
		DR 30/300	DR 30/300 SR 30/300	SR 30/300	SR 30/300	SR 30/300 SR 10/100
	L					



► Load Balancing



Comparison



Default Config.

Workload:

- Minimum DAQ effort
- Find missing 18 x FEBEX
- Find 2 missing EXPLODERS
- Modify 12DR32 into 8xDR48 (16k€)

Orders:

- 12 x SR32 30/300 (60 k€)
- 11 x SR32 10/100 (55 k€)
- + 3 spares (15 k€)
- Modify 2 FEBEX CRATES (4 k€)
- 18 new FEBEX Cards (20 k€)

Sum: **170k€**



As planned



Issues with punch through at 42-60°

4π Config.

Workload:

- Minimum DAQ effort
- Find missing 18 x FEBEX
- Find 2 missing EXPLODERS

Orders:

- 8 x DR 48 30/300 (60 k€)
- 8 x SR32 30/300 10/100 (40 k€)
- 11 x SR32 10/100 (55 k€)
- + 3 spares (15 k€)
- Modify 4 FEBEX CRATES (8 k€)
- 54 new FEBEX Cards (60 k€)
- Low voltage extension (20 k€)

Sum: **248k€**



All features in - 4π save



More data, less spares Two more racks needed

Mixed Config.

Workload:

- Some DAQ effort
- Find missing 18 x FEBEX
- Find 2 missing EXPLODERS
- Modify 16xSR-DR mixed (16k€)

Orders:

- 8 x DR 48 30/300 (60 k€)
- 8 x SR32 30/300 10/100 (40 k€)
- + 3 spares (15 k€)
- Modify 2 FEBEX CRATES (4 k€)
- 36 new FEBEX Cards (40 k€)

Sum: **180k€**



All features in - 4π save



More modifications @ Mesytec











Thank you!

CALIFA @ Technical University of Munich (TUM)

Roman Gernhäuser, Lukas Ponnath, Philipp Klenze, Tobias Jenegger









Tobias Jenegger